
RID	CET	Na
	JE I	NO.

PROJECT OWNER CONTRACT DRAWINGS FOR PROJECT NAME ANYTOWN, ME **MONTH YEAR**

NOTE


This set of plans is meant to portray an example of final construction drawings only, and must be accompanied by sufficient additional documentation of site conditioins to satisfy the need for the **Programmatic Notification Form. That** documentation would include elements such as stream profile, cross-section(s), substrate characterization, hydrology and hydaulics analysis.



DRAWING NO.

TITLE

EXISTING AND PROPOSED PLANS AND SECTIONS ROADWAY PLAN AND PROFILE TEMPORARY WATER CONTROL PLAN




LOCATION PLAN


WRIGHT-PIERCE ~
Engineering a Better Environment


Offices Throughout New England 888.621.8156 | www.wright-pierce.com


FOR REVIEW	
FOR BIDDING	

WP PROJECT NO. XXXXXX











SILT FENCE INSTALLATION



TEMPORARY HAY BALE SEDIMENT BASIN



SCALE: "NTS"

CONSTRUCTION SEQUENCING:

- 1. INSTALL APPLICABLE UPLAND EROSION AND SEDIMENTATION CONTROLS AT THE SITE.
- 2. MOBILIZE APPLICABLE EQUIPMENT AND MATERIALS
- 3. COMMENCE TREE CLEARING, STUMPING, AND GRUBBING. WORK MAY NOT OCCUR WITHIN THE WATERBODY UNTIL AFTER JULY 15 OR AS SPECIFIED IN THE PERMIT.
- 4. COORDINATE TRAFFIC CONTROL PLAN WITH THE ENGINEER AND APPLICABLE AUTHORITIES (PUBLIC WORKS, MDOT OR OTHERWISE).

PHASE "A" TO COMMENCE AFTER JULY 15:

- 1. COMMENCE CLOSURE OF THE ROADWAY TO VEHICULAR TRAFFIC.
- 2. INSTALL UPSTREAM AND DOWNSTREAM COFFERDAMS.
- 3. MAINTAIN BYPASS FLOWS THROUGH THE EXISTING CULVERT. AT NO TIME DURING CONSTRUCTION SHALL FLOW BE BLOCKED COMPLETELY. A MINIMUM AQUATIC BASEFLOW SHALL BE BYPASSED AT ALL TIMES, AS DETERMINED BY THE PERMITING AUTHORITES AND AS
- 4. INSTALL WORK ZONE DEWATERING SYSTEM. ENSURE THAT DEWATERING DISCHARGES ARE DIRECTED TO AN STABILIZED DISCHARGE AREA IN AN APPROVED UPLAND LOCATION. COORDINATE THE EXACT LOCATION AND BMPS TO BE UTILIZED WITH THE ENGINEER.
- 5. COMMENCE REMOVAL OF PAVEMENT AND EXCAVATION TO SUBGRADE FOR THE NEW CULVERT
- MAINTAIN THE DEWATERIGN SYSTEM AS NEEDED TO ENSURE THAT WORK OCCURS IN THE DRY. MAINTAIN ALL ASSOCIATED DEWATERING BMPS AS NEEDED TO MEET THE REQUIREMENTS OF THE PERMIT AS DIRECTED BY THE ENGINEER.
- 7. STOCKPILE NATIVE STREAM MATERIALS FOR REUSE AS BACKFILL. COORDINATE STOCKPILE LOCATION WITH THE ENGINEER AND PROVED APPROPRIATE EROSOIN AND SEDIMENTATION CONTROL BMPS AROUND THE STOCKPILE AREA.
- 8. PROOFROLL OR OTHERWISE PREPARE THE UNDISTURBED SUBGRADE FOR CULVERT PLACEMENT.
- 9. COMMENCE INSTALLATION OF LOWER BOX CULVERT SECTIONS.
- 10. COMMENCE INSTALLATION OF STREAM BANK BOULDERS TO THE LINES AND GRADES SHOWN ON THE PLANS. 11. FILL AREAS WITHIN THE CULVERT WITH NATIVE STREAM BED MATERIALS TO THE LINES AND
- GRADES SHOWN ON THE PLANS
- 12. FILL VOIDS WITHIN THE STREAM BANK BOULDERS BY CHOKING THE INTERSTITIAL SPACES WITH NATIVE STREAM BED MATERIAL.
- 13. COMPLETE INSTALLTION OF LOWER BOX CULVERT SECTIONS.
- 14. COMPLETE INSTALLATION OF STREAM BANK BOULDERS WITHIN THE PHASE A WORK AREA.
- 15. COMPLETE BACKFILLING OF CULVERT WIITH NATIVE STREAM BANK MATERIAL.
- 16. COMMENCE INSTALLTION OF UPPER BOX CULVERT SECTIONS.
- 17. COMMENCE INSTALLATION OF HEADWALL AND WINGWALL STRUCTURES WITHIN THE PHASE A WORK AREA
- 18. COMMENCE FILLING AND BACKFILLING OF BOX CULVERT AND HADWALL/WINGWALLS STRUCTURES TO EMBANKMENT GRADES AND ROADWAY SUBGRADE.
- 19. MAINTAIN APPROPRIATE EROSION AND SEDIEMENTATOIN CONTROLS, SUCH AS SILT FENCING AROUND THE PERIMITER OF ALL DISTURBED AREAS.
- 20. PERMANENTLY STABILIZE EMBANKMENT SLOPES WITHIN THE PHASE A WORK AREA.
- 21. COMMENCE REMOVAL OF PHASE A DEWATERING SYSTEM
- 22. COMMENCE REMOVAL OF PHASE A COFFER DAMS.
- 23. DIRECT STREAM FLOW THROUGH THE CONSTRUCTED STREAM BED AND BOX CULVERT
- 24. TEMPORARILY STABILIZE ANY OTHER REMAINING LOCATIONS WITHIN THE PHASE A WORK AREA.

PHASE "B" TO BE COMPLETED BEFORE SEPTEMBER 30:

- 1. MAINTAIN ROADWAY CLOSURE IN CONFORMANCE WITH THE TRAFFIC CONTROL PLAN.
- 2. INSTALL UPSTREAM AND DOWNSTREAM COFFERDAMS.
- 3. MAINTAIN FLOWS THROUGH THE NEW CULVERT. AT NO TIME DURING CONSTRUCTION SHALL FLOW BE BLOCKED COMPLETELY. A MINIMUM AQUATIC BASEFLOW SHALL BE BYPASSED AT ALL TIMES, AS DETERMINED BY THE PERMITING AUTHORITES AND AS DIRECTED BY THE ENGINEER.
- 4. INSTALL WORK ZONE DEWATERING SYSTEM. ENSURE THAT DEWATERING DISCHARGES ARE DIRECTED TO AN STABILIZED DISCHARGE AREA IN AN APPROVED UPLAND LOCATION. COORDINATE THE EXACT LOCATION AND BMPS TO BE UTILIZED WITH THE ENGINEER.
- 5. COMMENCE REMOVAL OF PAVEMENT AND EXCAVATION TO REMOVE THE EXISTING CULVERT
- 6. COMPLETE REMOVAL OF THE EXITING CULVERT
- 7. COMMENCE EXCAVATION TO SUBGRADE FOR REMAINING STREAM BANK BOULDERS
- 8. COMMENCE INSTALLATION OF REMAINING STREAM BANK BOULDERS.
- 9. COMPLETE STREAM BANK BOULDER INSTALLATION AND FILL VOIDS WITH BETWEEN THE STREAM BANK BOULDERS WITH NATIVE MATERIALS.
- 10. COMMENCE INSTALLTION OF REMAINING HEADWALL AND WINGWALL STRUCTURES
- 11. COMMENCE BACKFILL OF THE HEADWALL/WINGWALLS.
- 12. PLACE FILL AND BACKFILL TO EMBANKMENT GRADES AND ROADWAY SUBGRADE.
- 13. PERMENANTLY STABILIZE ALL EMBANKMENTS WITHIN THE PHASE B WORK AREA.
- 14. COMMENCE REMOVAL OF PHASE B DEWATERING SYSTEMS.
- 15. COMMENCE REMOVAL OF PHASE B COFFER DAMS.
- 16. COMPLETE PHASE B WORK AND ALL WORK WITHIN THE WATER OR WETLANDS.

WORK TO BE COMPLETED AFTE R PHASE B:

- 1. COMMENCE INSTALLATOIN OF ROADWAY GRAVELS
- 2. COMMENCE INSTALLATION OF BINDER PAVEMENT
- 3. COMMENCE INSTALLATION OF ROADWAY AND TRAFFIC CONTROL DEVICES, SUCH AS GUARDRAIL, AS INDICATED ON THE PLANS.
- 4. COMPLETE PERMENANT STABILIZATION ON ALL AREAS DISTURBED BY CONSTRUCTION. ALL AREAS NOT RECIEVING STRUCTURAL STABILIZATION MEASURES SHALL BE PERMENENTLY STABILIZED WITH LOAM, SEED, AND MULCH. EROSION CONTROL BLANKETS MAY ALSO BE REQUIRED DEPENDING ON TIME OF YEAR AND
- 5. COMMENCE AND COMPLETE INSTALLATION OF FINAL PAVING
- 6. IN CONFORMANCE WITH THE TRAFFIC CONTROL PLAN, REPOEN THE ROADWAY TO VEHICULAR TRAFFIC. COORDINATE REOPEINGING WITH THE APPROPRIATE AUTHORITY (PUBLIC WORKS, MDOT, ETC..) AND THE ENGINEER.
- 7. COMPLETE ALL PERMENANT STABILIZATION.
- 8. DEMOBILIZE REMAINING EQUIPMENT AND MATERIALS FROM THE PROJECT AREA
- 9. REMOVE REMAINIGN EROSION AND SEDIMENTATION CONTROLS.

